



NOTES

1. INLET CAN BE PRECAST MANUFACTURED CONCRETE UNIT OR CAST IN PLACE DESIGNED FOR H-20 LOADING.
2. REINFORCING SHALL BE #4 BARS @ 12" O.C. (MAX.) EACH WAY OR 4"x4"-6-6 GAUGE W.W.F. IN THE WALL AND BASE.
3. ADD 2" CONCRETE COLLAR FOR DETACHED SIDEWALK.
4. PLACE CAST IRON HOOD, FRAME AND GRATE. D&L FOUNDRY MODEL I-3541, 3542, 3543 OR EQUAL.
5. STAMP DRAIN INLETS "NO DUMPING DRAINS TO RIVER".
6. SUBGRADE TO BE APPROVED BY ENGINEER OR GEOTECH PRIOR TO PLACEMENT OF CRUSHED ROCKS.

YUBA COUNTY DEPARTMENT OF PUBLIC WORKS	
DRAIN INLET	
APPROVED BY: <i>Donald P. Peters</i>	DATE: 8/11/23
402	